

# MANHATTAN WEST

**Project Location:**  
New York City, New York

**Client:**  
Rizzani De Eccher, USA

**Precast Value:**  
Approximately \$16 Million



## Project Description:

Precast work involves fabrication of 612 post-tensioned bridge segmental precast units to produce 16 bridge spans for use to bridge an open space above the railroad tracks in NY City for a real estate developer. Project used 4.5M lbs. of reinforcing bars. Each segment weighs in excess of 50 tons. Fabrication involves sophisticated geometry control system performed by internal quality control personnel. Trucking was performed in house.

